37	49	providing 20mm thk cement plaster in single coat with cement mortar 1:4 to stone/brick/aerocon block/block masonary and concrete surface including rounding off corners wherever required smooth rendering,providing and removing scaffolding including cost of materials,labour and curing complete as per specifications....external alround wall	sqm	244.80	390.00	Rupees Three Hundered Ninty Only
				172.54	290.38	Rupees Two Hundered ninty,thirty eight paisa only
38	50	providing 20mm thk cement plaster in single coat with cement mortar 1:4 to stone/brick/aerocon block/block masonary and concrete surface including rounding off corners wherever required smooth rendering,providing and removing scaffolding including cost of materials,labour and curing complete as per specifications....First floor	sqm	221.97	390.00	Rupees Three Hundered Ninty Only
39	51	providing 20mm thk cement plaster in single coat with cement mortar 1:4 to stone/brick/aerocon block/block masonary and concrete surface including rounding off corners wherever required smooth rendering,providing and removing scaffolding including cost of materials,labour and curing complete as per specifications....parapet wall	sqm	210.75	390.00	Rupees Three Hundered Ninty Only
40	52	KSRB15-3.1 : Providing 12mm thick cement plaster in single coat with cement mortar 1:4; to brick masonary & concrete surface including rounding off corners wherever required smooth rendering,: providing and removing scaffolding,including cost of all materials, labour,curing complete as per specificiations Internal walls	sqm	308.43	390.00	Rupees Three Hundered Ninty Only
				257.62	204.75	Rupees Two Hundered Four,seventy five paisa only

Executive Engineer
RR Nagar Division

Scanned by CamScanner

41	53	KSRB15-3.1 : Providing 12mm thick cement plaster in single coat with cement mortar 1:4; to brick masonary & concrete surface including rounding off corners wherever required smooth rendering,: providing and removing scaffolding,including cost of all materials, labour,curing complete as per specificiations.....first floor	sqm	308.43	390.00	Rupees Three Hundered Ninty Only
				59.02	204.75	Rupees Two Hundered Four,seventy five paisa only
42	54	KSRB15-3.1 : Providing 12mm thick cement plaster in single coat with cement mortar 1:4; to brick masonary & concrete surface including rounding off corners wherever required smooth rendering,: providing and removing scaffolding,including cost of all materials, labour,curing complete as per specificiations.....second floor	sqm	194.68	390.00	Rupees Three Hundered Ninty Only
43	55	providing 12mm thk cement plaster in single coat with cement mortar 1:3, to ceilling,beam sides including rounding off corners wherever required smooth rendering;providing and removing scaffolding,including cost of materials,labour,curing complete as per specifications....Ground floor	sqm	228.90	390.00	Rupees Three Hundered Ninty Only
44	56	providing 12mm thk cement plaster in single coat with cement mortar 1:3, to ceilling,beam sides including rounding off corners wherever required smooth rendering;providing and removing scaffolding,including cost of materials,labour,curing complete as per specifications....First floor	sqm	241.14	390.00	Rupees Three Hundered Ninty Only
45	57	providing 12mm thk cement plaster in single coat with cement mortar 1:3, to ceilling,beam sides including rounding off corners wherever required smooth rendering;providing and removing scaffolding,including cost of materials,labour,curing complete as per specifications....second floor	sqm	41.95	390.00	Rupees Three Hundered Ninty Only

ntractor

Executive Engineer

Scanned by CamScanner

46	58	providing rough cement plastering 15mm thk in single coat with cement mortar 1:4,to block masonary/concrete surface for base of dadoing work with sand of approved quality ,providing & removing scaffolding,including cost of materials,labour,curingas per specifications.....Toilets	sqm	52.40	390.00	Rupees Three Hundered Ninty Only
				43.60	230.81	Rupees Two Hundered Thirty, eighty one paisa only
47	59	providing rough cement plastering 15mm thk in single coat with cement mortar 1:4,to block masonary/concrete surface for base of dadoing work with sand of approved quality ,providing & removing scaffolding,including cost of materials,labour,curingas per specifications....first floor	sqm	37.50	390.00	Rupees Three Hundered Ninty Only
48	61	Providing lime rendering for plastering to walls and ceilling,including cost of all materials,labour,curing complete as per specification.	sqm	381.49	390.00	Rupees Three Hundered Ninty Only
				333.25	31.02	Rupees thirty one only
49	62	Providing lime rendering for plastering to walls and ceilling,including cost of all materials,labour,curing complete as per specification.first floor	sqm	381.49	390.00	Rupees Three Hundered Ninty Only
				245.41	31.02	Rupees thirty one only
50	63	Providing lime rendering for plastering to walls and ceilling,including cost of all materials,labour,curing complete as per specification.second floor	sqm	236.63	390.00	Rupees Three Hundered Ninty Only
	64	providing and fixing 20mm thick gang saw water cut sadarahalli grey granite in CM 1:4 proportion ,cut to required shape,pattern with paper joints,finished pigments to match the colour of slab making through jointing with sealant,grooves in joints including cost of curing	sqm	62.32	2,000.00	Rupees Two Thousand Only
	65	providing and fixing special make glazed vitrified tiles (Granomite finish) of approved make,quality and colour of size 600*600*10mm thick fixed on existing flooring with a special roffe adhesive for flooring and skirting etc...,complete including providing spears at required size and fixing etc....flooring	sqm	126.75	1,300.00	Rupees One Thousand Three Hundered Only

Scanned by CamScanner

53	66	providing and fixing special make glazed vitrified tiles (Granomite finish) of approved make,quality and colour of size 600*600*10mm thick fixed on existing flooring with a special roffe adhesive for flooring and skirting etc...,complete including providing spears at required size and fixing etc....first floor	sqm	199.18	1,300.00	Rupees One Thousand Three Hundered Only
54	67	providing and fixing special make glazed vitrified tiles (Granomite finish) of approved make,quality and colour of size 600*600*10mm thick fixed on existing flooring with a special roffe adhesive for flooring and skirting etc...,complete including providing spears at required size and fixing etc....second floor	sqm	22.90	1,300.00	Rupees One Thousand Three Hundered Only
55	68	KSRB 14,14-5: providing colour ceramic (antiskid) tiles of approved make,shade & size 30*30 cms for flooring,treads of steps and landings laid on a bed of 12mm thk cement mortar1:3 mix flush pointing with white cement using colour pigment,including cost of materials,labour specification noKBS.....ground floor	sqm	15.00	1,300.00	Rupees One Thousand Three Hundered Only
56	69	KSRB 14,14-5: providing colour ceramic (antiskid) tiles of approved make,shade & size 30*30 cms for flooring,treads of steps and landings laid on a bed of 12mm thk cement mortar1:3 mix flush pointing with white cement using colour pigment,including cost of materials,labour specification noKBS.....First floor	sqm	12.50	1,300.00	Rupees One Thousand Three Hundered Only
57	71	KSRB 14,17.1: Providing skirting,dado rises colour glazed tiles 30*60cms on 6mm thick with border of size 30*10 cms on 10mm thick cement plaster 1:3 and joined with white cement slurry over rough plaster surface(excluding cost of rough plastered surfaces which should be measured and paid separately)using glazed tiles of approved make,and size including cost of material labour,complete as per specifications.	sqm	26.00	1,300.00	Rupees One Thousand Three Hundered Only

Contractor

Executive Engineer
RR Nagar Division

Scanned by CamScanner

				24.00	1,841.53	Rupees One Thousand eight hundered fourty one,fifty three paisa only
58	72	KSRB 14.17.1: Providing skirting,dado rises colour glazed tiles 30*60cms on 6mm thick with border of size 30*10 cms on 10mm thick cement plaster 1:3 and joined with white cement slurry over rough plaster surface(excluding cost of rough plastered surfaces which should be measured and paid separately)using glazed tiles of approved make,and size including cost of material labour,complete as per specifications. first floor	sqm	26.00	1,300.00	Rupees One Thousand Three Hundered Only
				6.25	1,841.53	Rupees One Thousand eight hundered fourty one,fifty three paisa only
59	77	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after throughly brushing the surface,free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials,labour,complete as per specifications. with primer.....same as inside plastering	sqm	670.91	100.00	Rupees One Hundered Only
60	78	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after throughly brushing the surface,free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials,labour,complete as per specifications. with primer.....First floor	sqm	626.90	100.00	Rupees One Hundered Only

ntractor

Executive Engineer
RR Nagar Division

Scanned by CamScanner

61	79	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after throughly brushing the surface,free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials,labour,complete as per specifications. with primer.....second floor	sqm	236.63	100.00	Rupees One Hundered Only
62	80	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material,free from mortar drops and other foreign matter cost of materials,labour,complete as per specificiations.....same as inside plastering	sqm	243.75	100.00	Rupees One Hundered Only
				470.99	104.24	Rupees One Hundered four,twenty four paisa only
63	81	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material,free from mortar drops and other foreign matter cost of materials,labour,complete as per specificiations.....First floor	sqm	243.75	100.00	Rupees One Hundered Only
				383.15	104.24	Rupees One Hundered four,twenty four paisa Only
64	82	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material,free from mortar drops and other foreign matter cost of materials,labour,complete as per specificiations.....second floor	sqm	236.63	100.00	Rupees One Hundered Only

Executive Engineer
RR Nagar Division

Scanned by CamScanner

65	83	providing and fixing stainless steel staircase railling as per chief architect drawing no.11520/HSRSC with hand rail 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage,stainless steel vertical pipe spaced at 1.2m regular intervals,and 5 nos of 25mm dia.stainless steel hollow horizontal pipe welded to vertical 50mm dia hollow pipe. the entire assembly is fixed to staircase concrete by expansion bolts by drilling concrete etc..,complete including cost of materials,labour,HOM of machineries and electrical charges,etc., complete as per specifications.	sqm	33.75	5,800.00	Rupees Five Thousand Eight Hundered Only
				13.05	7,627.94	Rupees Seven Thousand Six Hundred twenty seven,ninty four paisa only
66	84	providing and fixing factory made single leaf rigid GRP sandwich composite door shutter of 40mm thick, laminated with two GRP skins with wood grain finish,fabricated using U.V-stabilized isophalic gelocoat and one layer of 450grms E-glass chopped strand mat (CSM).Impregnated with orthopthalic polyester resin, the thickness of the skins shall not be less than 1.5mm.expanded polystyrene (EPS) structural foam panel of 37mm thickness and a density of 20kg/m3 shall be used as core material.wooden reinforcements made of seasoned salwood block of cross section not less than 36mm*32mm and also necessary salwood reinforcements for fixing the metal fitting such as tower bolts,aldrops,handles,etc.shall be provided, a structural adhensive compatible with EPS foam shall be used for bonding the core material, the salwood reinforcement and the skins. the material and process for manufacturing the door shutters shall confirm to RV-	sqm	9.00	4,000.00	Rupees Four Thousand Only

Executive Engineer
RR Nagar Division

Scanned by CamScanner

67	85	providing and fixing factory made single leaf rigid GRP sandwich composite door shutter of 40mm thick, laminated with two GRP skins with wood grain finish,fabricated using U.V-stabilized isophalic gelocoat and one layer of 450grms E-glass chopped strand mat (CSM),Impregnated with orthopthalic polyester resin, the thickness of the skins shall not be less than 1.5mm.expanded polystyrene (EPS) structural foam panel of 37mm thickness and a density of 20kg/m3 shall be used as core material.wooden reinforcements made of seasoned salwood block of cross section not less than 36mm*32mm and also necessary salwood reinforcements for fixing the metal fitting such as tower bolts,aldrops,handles,etc.shall be provided, a structural adhensive compatible with EPS foam shall be used for bonding the core material, the salwood reinforcement and the skins. the material and process for manufacturing the door shutters shall confirm to RV-	sqm	9.00	4,000.00	Rupees Four Thousand Only
68	87	KSRB 9.4-2 : providing honne wood frames of doors,windows,ventilators & other frames,wrought,framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps),but including cost of materials,labour,HOM of machineries complete as per specifications.	cum	0.81	1,14,980.50	Rupees One Lakh Fourteen Thousand Nine Hundered Eighty,fifty paisa only
69	88	KSRB 9-1 0.1 : providing and fixing in position honne wood class-II fully pannelled shutters for doors,styles and rails of 35mm.thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick,4mm thick plain glass,fixed with beading 15mm wide and thickness to finish with shutters surface including cost of materials,labour,HOM of macheneries complete as per specifications.(excluding cost of fixtures)	sqm	26.33	5,000.00	Rupees Five Thousand Only

ntractor

Executive Engineer
RR Nagar Division

Scanned by CamScanner

70	89	Providing & fixing in position anodised aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame of size 61.85*31.75mm bottom section 1.2mm thick,weight 0.695kg/m,sides and top section 1.3mm,thick,weight 0.695kg/m,shutter comprising top and bottom section of size 40mm*18mm,wall thickness 1.25mm,weight 0.417kg/m,shutter outer side 40mm*18mm,wall thickness 1.25mm,weight 0.417 kg/m,shutter interlock section 40mm*26.7mm wall thickness 1.1mm,thick,weight 0.469kg/m,the shutter mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.,providing and fixing 5.5mm,thick plainglass for shutters fitted with rubber beading all aluminium sections powered coated to a minium of 60-70 microns with exterior durable pur polyester grade powder of approved quality including cutting to required length joints mitred	sqm	27.54	4,000.00	Rupees Four Thousand Only
71	90	Providing & fixing in position anodised aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame of size 61.85*31.75mm bottom section 1.2mm thick,weight 0.695kg/m,sides and top section 1.3mm,thick,weight 0.695kg/m,shutter comprising top and bottom section of size 40mm*18mm,wall thickness 1.25mm,weight 0.417kg/m,shutter outer side 40mm*18mm,wall thickness 1.25mm,weight 0.417 kg/m,shutter interlock section 40mm*26.7mm wall thickness 1.1mm,thick,weight 0.469kg/m,the shutter mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.,providing and fixing 5.5mm,thick plainglass for shutters fitted with rubber beading all aluminium sections powered coated to a minium of 60-70 microns with exterior durable pur polyester grade powder of approved quality including cutting to required length joints mitred	sqm	35.10	4,000.00	Rupees Four Thousand Only

ntractor

Executive Engineer
RR Nagar Division

Scanned by CamScanner